




15		16		17		18	
REFERENCE DOCUMENTS							
P&ID LEGEND				PRO13-ING-PROO			
PROCESS FLOW DIAGRAM				21044-PR-PID-00000			
UTILITY FLOW DIAGRAM				PRO10-ING-PRO1/02/03/04			
MATERIAL SELECTION DIAGRAM				21044-PR-PFD-00001			
				PRO10-ING-PR11			
				21044-PR-UFD-00001			
				PRO08-ING-FR01			
				21044-PR-MSD-00001			
ISA 0X				INSTRUMENT SUPPLY AIR			
V 0X				VENT			
E-371 NGL VAPORIZER HEATER				E-372 NRU VAPORIZER HEATER			
DESIGN DUTY 200 kW				DESIGN DUTY 260 kW			
DESIGN PRES. COLD S. 15 bar g				DESIGN PRES. COLD S. 15 bar g			
DESIGN TEMP. COLD S. -196/150 °C				DESIGN TEMP. COLD S. -196/150 °C			
DESIGN PRES. HOT S. 15 bar g				DESIGN PRES. HOT S. 15 bar g			
DESIGN TEMP. HOT S. -196/150 °C				DESIGN TEMP. HOT S. -196/150 °C			
CORR. ALL. COLD/HOT 0 mm				CORR. ALL. COLD/HOT 0 mm			
INSULATION H (50 mm)				INSULATION H (50 mm)			
MATERIAL COLD SIDE PLATES SS316				MATERIAL COLD SIDE PLATES SS316			
MATERIAL HOT SIDE PLATES SS316				MATERIAL HOT SIDE PLATES SS316			
SURFACE AREA 14.4 m2				SURFACE AREA 35.4 m2			
NOTES							
1 AT THE START UP FUEL GAS WILL BE PROVIDED BY RAW GAS FROM V-201. AFTER START UP MANUAL VALVES AND CONTROL VALVE IN THIS LINE SHALL BE CLOSED.							
2 DRAIN ON THE LOWEST POINT FOR DRAINING C5+ FROM COLD BOX AFTER PLANT SHUT DOWN.							
3 LINE AND CONTROL VALVE DESIGNED FOR TOTAL FUEL GAS FLOW RATE REQUIREMENT.							
4 FIRESAFE GLOBE VALVE							
5 PV-3731 CAN NOT OPEN UNLESS TEMPERATURE UPSTREAM IS ABOVE TAL-2001. PLC LOGIC WILL HAVE A PERMISSIVE FOR THIS PURPOSE, USING TAL-2001.							
----- TAM SUPPLY LIMIT							